

JakMat Preparation for Footpath



1. Gap 7 was used for sub-base.



2. Hand or power tools can



3. Filled the cells with 9 - 18mm Kauai River Stones



4. A small amount of excess was allowed for settlement







Jakaar Industries Ltd

PO Box 204069, Highbrook, Manukau 2161, Auckland, New Zealand Tel +64 9 273 5511, Fax +64 9 273 5512

www.jakmat.co.nz

66 Cryers Rd, Highbrook, Manukau 2013